



# TECHNICAL SPECIFICATION OF FORMWORK AND SEGMENT HANDLING EQUIPMENT

# TABLE OF CONTENTS

ABLE OF CONTENTS	1
SEGMENTS MOULDS: TECHNICAL SPECIFICATIONS	2
SERVICES	2
QUALITY PROCESS	3
MANUFACTURE FEATURES	4
OLERANCES	5
DPENING/CLOSE/CENTERING SYSTEMS	6
PNEUMATIC VIBRATORS	7
SEGMENT HANDLING EQUIPMENT: TECHNICAL SPECIFICATIONS	8

This document contains confidential info of KOREA MOULD property.





# SCOPE OF THE SUPPLY

The supply includes the manufacture of segments moulds. Precast segments are parts of the ring as tunnel lining excavated by TBM.

# SEGMENTS MOULDS: TECHNICAL SPECIFICATIONS

Technical description for the manufacture of SEGMENTS STEEL MOULDS for the production of Tunnel precast segments.

Segments moulds type	Stationary
Number of moulds / ring	Nr.
Number of sets	Nr.
Side opening	Manual
Vibration	External pneumatic vibrators
Warranty	The entire duration of the project



## SERVICES

Technical and commercial info with the Client Periodical check for the warranty of the quality of the segments moulds Segments moulds design Delivery Timetable Quality Control and Final Acceptance of the segments moulds Supply for Segments Moulds (EXWorks condition including packaging)





# **QUALITY PROCESS**

## DESIGN

Drawings processing and technical documents registration Design drawings processing and registration

## COORDINATION

Periodical control for the supply Acceptance of incoming materials (quality and quantity)

#### MANUFACTURE

Reception of design drawings Manufacture of the segments moulds in according to design & drawings Cut and moulding processes Mechanical operations Welding process Assembly and final check and setting

## CONTROL

Final check of the components and reports certified by the Coordinator Non-Compliance survey Final dimensional check of the segments moulds based on Acceptance protocol Commissioning protocol

## **QUALITY DEPT**

Control based on technical requirements





## **MANUFACTURE FEATURES**

#### LOWER STRUCTURE

ASTM A36 steel grade : Korean Standard: KS D 3503 – SS400,SS490 – Posco Steel Laser cutting and calender by cold process and properly reinforced steel 12 mm thick steel plate as final thickness Conical centering pin of high precision at both side walls Access to the lower structure of the mould for inspection of vibrators

## SIDE and FRONT WALLS



Mobil front walls (ASTM A36 steel grade) 33 mm thick as starting machined steel plate Conical centering pin of high precision Special rubber seals between the side walls and front walls and bottom of the mould

Two fast closing taps on top with springs to keep them open while doing ceaning and preparing for concreting.

Mobil machined side walls designed to ensure a robust structure to endure all conditions during the precast works (ASTM A36 steel grade - 33 mm thick as starting machined steel plate).



WELDING MIG welding processes

SURFACE PROTECTION OF SEGMENTS MOULDS Layer of coating (painting) should be composed of two components,  $80/120 \ \mu m$ .

#### **ASTM A36 STEEL GRADE PROPERTIES**

ASTM A36 is a construction carbon steel with ductility properties ASTM A36 has min 250 MPa yield strength and 400-550 MPa ultimate tensile strength.





# TOLERANCES

The segments moulds are engineered and designed in according to Client requirements and manufactured and tested in according to ISO 9001-2008.

Segment length	± 0.5 mm
Circumpherential length	± 0.6 mm
Thickness	0 -3 mm
Diagonal chord	± 1.0 mm
Longitudinal and radial face planarity	± 0.5 mm
Allowable bend into the lower structure	± 1.5 mm
Groove dimensions (gaskets)	± 0.3 mm
Tolerance into the lower groove due to rotation or faces deformation	± 0.3 mm
Inserts position	± 1.0 mm





# **OPENING/CLOSE/CENTERING SYSTEMS**



The side walls are connected to the mould structure by a tubeshaped bar.

A tailored hinge regulates the opening.

Onto the side walls are fitted bushings where will be placed the centering cones.

The side walls are blocked by screws.

The screws determine the contact between side wall and plate (cone location).

The front walls are centering and blocked to the mould structure with the same solution as per the side walls.

Onto the front walls will be fitted other centering cones that shall be coupled with the bushings inserted onto the side walls.

This solution defines precisiously the position of the side walls and the front walls into the space assuring that the precast segments shall be poured in according to the design requirements in terms of tolerances.



Onto the side walls and front walls are visible the matching signs (the perfect alignment of these signs gives a fast reply about the closure of the segment mould).





# **PNEUMATIC VIBRATORS**

Each segment mould is equipped with external pneumatic vibrators in order to guarantee a correct spread and filling of the poured concrete on the full surface of the mould.

The vibration force resonates with the lower surface of the mould and has been specially designed so as not to influence the dimensional quality of the perimeter facades (whose tolerances is in the order of tenth of a millimetre) creating neither distortions nor tesnions to the structure of the segment mould. The external vibrators are fixed to the frames of the lower structure of the mould on vibratio diffusion bars.

Each vibrator should be supplied by a separate distribution line of compressed air provided with a quickclosing ball valve.

Air compressor and air storage tank are not included in the scope of supply.



Frequency	14.500 vpm
Centrifugal force	61,18 kN
Air consumption	1.800 l/min
Working pressure	6 Bar
Assembly of vibrators	The support of the pneumatic vibrators is
	designed to guarantee the highest number
	of cycles without any failure and crack





# SEGMENT HANDLING EQUIPMENT: TECHNICAL SPECIFICATIONS

## **Vacuum Lifting Device**



-Demoulding the segment and transport of the segments to the tilting station.

-Individual remote controller

-Crane hook type

## Segment tilting device



-Control Pannels

-Hydraulic sytem and control unit included

# Vacuum demould and tilting device - extrados surface of segment



- Demoulding the segment and 180 degree tilting
- Individual remote controller
- Crane hook type